

ABSTRACT

In the construction industry, aside to carry through the specified work targets, it is important to always make improvements both of technical and managerial. The example one of those improvements is to build a good work culture. The work culture will be able to boost productivity internally. The work culture that is used as reference in the research is the 5S from Japan. 5S stands for *Seiri, Seiton, Seiso, Seiketzu, and Shitsuke* and it is more well-known in Indonesia as 5R Principle, stands for Ringkas, Rapi, Resik, Rawat, and Rajin.

The research was carried out by analyzing video documentation, which is observing at each stage of the video documentation of pad-footing's work and brick installation to find problems according to 5R principle.

The result of research is to give example of the common problem that happens in the construction site and to give a suggestion about best practice for pad-footing's work and brick installation.

Keyword : 5S, Best Practice, Work Culture, Improvement

INTISARI

Dalam proses pembangunan, penting untuk terus melakukan perbaikan baik secara teknis maupun sistem dalam memenuhi sasaran pekerjaan yang telah ditentukan. Salah satu bentuk upaya perbaikan tersebut adalah dengan penerapan budaya kerja yang baik. Budaya kerja akan mampu meningkatkan kualitas kinerja secara internal yang mampu mendongkrak efisiensi dan efektifitas kerja. Pada penelitian ini budaya kerja yang dijadikan acuan adalah budaya kerja 5S dari negara Jepang. 5S adalah singkatan dari *Seiri*, *Seiton*, *Seiso*, *Seiketsu* dan *Shitsuke*. Budaya kerja 5S ini lebih dikenal di Indonesia dengan prinsip 5R, yaitu Ringkas, Rapi, Resik, Rawat dan Rajin.

Metode penelitian yang digunakan adalah studi dokumen, yaitu melakukan pengamatan pada tiap tahap video dokumentasi pekerjaan pengecoran fondasi dan pemasangan bata untuk menemukan masalah pada masing-masing pekerjaan dengan konsep 5R.

Hasil yang didapatkan dari penelitian adalah gambaran umum pelaksanaan pekerjaan beserta usulan *best practice* dalam pekerjaan pengecoran fondasi dan pemasangan bata.

Kata Kunci : 5S, Best Practice, Budaya Kerja, Perbaik